

AD-A104 953

PRC CONSOER TOWNSEND INC ST LOUIS MO

F/6 13/13

NATIONAL DAM SAFETY PROGRAM. SMITH LAKE DAM (MO 11124), MISSISS--ETC(U)

DEC 80 W G SHIFRIN

DACW43-80-C-0094

NL

UNCLASSIFIED

1 OF 1  
AD A  
13-6 9-83

END  
DATE  
FILMED  
10-81  
DTIC




LEVEL

12

**MISSISSIPPI-SALT-QUINCY RIVER BASIN**

**AD A104953**

SMITH LAKE DAM  
PIKE COUNTY, MISSOURI  
MO. III24




**PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM**



**United States Army  
Corps of Engineers**  
... Serving the Army  
... Serving the Nation

**St. Louis District**



PREPARED BY: U. S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

"Original contains color  
plates: All black and white  
reproductions will be in black and  
white"

DECEMBER 1980

**81 10 2 147**

**DTIC FILE COPY**



UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	10-A304953	
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Smith Lake Dam (MO 11124) Pike County, Missouri		5. TYPE OF REPORT & PERIOD COVERED (7) Final Report.
7. AUTHOR(s) Consoer, Townsend and Associates, Ltd.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) (15) DACW43-80-C-0094
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS (11)
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) (6) National Dam Safety Program. Smith Lake Dam (MO 11124), Mississippi - Salt - Quincy River Basin, Pike County, Missouri. Phase I Inspection Report.		12. REPORT DATE December 1980
16. DI Approved for release; distribution unlimited.		13. NUMBER OF PAGES Approximately 70
17. DISTRIBUTION STATEMENT (of the abstract entered in block 20, if different from report) CIC Walter - 12/1/80		15. SECURITY CLASS. (of this report) UNCLASSIFIED
18. SUPPLEMENTARY NOTES		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE (13) 84
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE


UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

410553



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

REF  
all  
Cl  
bas  
sym

COM

Block

retrie

uncle  
"Ab  
show  
title  
Make

dates

as  
are

order  
of the

which

of the  
repe

Dep  
"Re  
und

con  
Tec

offic

the  
abba

Dis

Ine  
und

...  
sup  
of

to  
reg  
it  
Ad





REPLY TO  
ATTENTION OF

**DEPARTMENT OF THE ARMY**  
**ST. LOUIS DISTRICT, CORPS OF ENGINEERS**  
210 TUCKER BOULEVARD, NORTH  
ST. LOUIS, MISSOURI 63101

SUBJECT: Smith Lake Dam (Mo. 11124) Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Smith Lake Dam (Mo. 11124).

It was prepared under the National Program of Inspection of Non-Federal Dams.

**SIGNED**

SUBMITTED BY: \_\_\_\_\_  
Chief, Engineering Division


**18 DEC 1990**

Date

APPROVED BY: \_\_\_\_\_  
Colonel, CE District Engineer

**22 DEC 1990**

Date





SMITH LAKE DAM  
PIKE COUNTY, MISSOURI

MISSOURI INVENTORY NO. 11124

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

PREPARED BY  
CONSOER, TOWNSEND AND ASSOCIATES, LTD.  
ST. LOUIS, MISSOURI  
AND  
PRC ENGINEERING CONSULTANTS, INC.  
ENGLEWOOD, COLORADO  
A JOINT VENTURE

UNDER DIRECTION OF  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS  
FOR  
GOVERNOR OF MISSOURI

DECEMBER 1980



PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Smith Lake Dam, Missouri Inv. No. 11124  
State Located: Missouri  
County Located: Pike  
Stream: An unnamed tributary of Noix Creek  
Date of Inspection: July 8, 1980

Assessment of General Condition

Smith Lake Dam was inspected by the engineering firms of Consoer, Townsend and Associates, Ltd. and PRC Engineering Consultants, Inc. (A Joint Venture) of St. Louis, Missouri according to the U. S. Army Corps of Engineers "Recommended Guidelines for Safety Inspection of Dams" and additional guidelines furnished by the St. Louis District of the Corps of Engineers. Based upon the criteria in the guidelines, the dam is in the high hazard potential classification, which means that loss of life and appreciable property loss could occur in the event of failure of the dam. Within the estimated damage zone of half a mile downstream of the dam are nine dwellings, two trailers, a railroad bridge, and a state highway (Hwy 79), which may be subjected to flooding, with possible damage and/or destruction, and possible loss of life. Smith Lake Dam is in the small size classification since it is less than 40 feet and more than 25 feet high, and impounds 49 acre-feet of water.



The inspection and evaluation by the consultant's inspection team indicate that the spillway of Smith Lake Dam does not meet the criteria set forth in the guidelines for a dam having the above size and hazard potential. Smith Lake Dam being a small size dam with a high hazard potential is required by the guidelines to pass from one-half of the Probable Maximum Flood to the Probable Maximum Flood without overtopping. Considering the number of inhabited dwellings and a major highway being located within half a mile downstream of the dam, the PMF is considered the appropriate spillway design flood for Smith Lake Dam. The Probable Maximum Flood is defined as the flood discharge that may be expected from the most severe combination of critical meteorological and hydrologic conditions that are reasonably possible in the region. It was determined that the reservoir/spillway system can accommodate approximately 65 percent of the Probable Maximum Flood without overtopping the dam. The evaluation also indicates that the reservoir/spillway system can accommodate the one-percent chance flood (100-year flood) without overtopping.

Other deficiencies noted by the inspection team were: the dumping of quarry spoils onto the downstream face and the top of dam, the trees and bushes in the spillway channel, the erosion in the spillway channel, lack of protection on the top of dam against surface runoff erosion, the cracks on the top of dam and downstream slope, the erosion gullies on the downstream slope, the trees growing on the dam embankment, the possible seepage areas downstream of the toe of the dam, the tall vegetation on the downstream slope, a need for periodic inspection by a qualified engineer and a lack of a maintenance schedule. The lack of seepage and stability analyses on record is also a deficiency that should be corrected. All burrowing animals should be eliminated from the embankment.



It is recommended that the owner take action to correct or control the deficiencies described above.

*Walter G. Shifrin*

Walter G. Shifrin, P.E.







Rock fragment from the impact site.



NATIONAL DAM SAFETY PROGRAM

SMITH LAKE DAM, I.D. No. 11124

TABLE OF CONTENTS

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 1	PROJECT INFORMATION . . . . .	1
	1.1 General . . . . .	1
	1.2 Description of Project . . . . .	3
	1.3 Pertinent Data . . . . .	7
SECTION 2	ENGINEERING DATA . . . . .	10
	2.1 Design . . . . .	10
	2.2 Construction . . . . .	10
	2.3 Operation . . . . .	10
	2.4 Evaluation . . . . .	10
SECTION 3	VISUAL INSPECTION . . . . .	12
	3.1 Findings . . . . .	12
	3.2 Evaluation . . . . .	18



TABLE OF CONTENTS

(Continued)

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 4	OPERATION PROCEDURES . . . . .	21
	4.1 Procedures . . . . .	21
	4.2 Maintenance of Dam . . . . .	21
	4.3 Maintenance of Operating Facilities . . . . .	21
	4.4 Description of Any Warning System in Effect . . . . .	21
	4.5 Evaluation . . . . .	22
SECTION 5	HYDRAULIC/HYDROLOGIC . . . . .	23
	5.1 Evaluation of Features . . . . .	23
SECTION 6	STRUCTURAL STABILITY. . . . .	26
	6.1 Evaluation of Structural Stability. . . . .	26
SECTION 7	ASSESSMENT/REMEDIAL MEASURES. . . . .	29
	7.1 Dam Assessment . . . . .	29
	7.2 Remedial Measures. . . . .	31



TABLE OF CONTENTS

(Continued)

LIST OF PLATES

	<u>Plate No.</u>
LOCATION MAP . . . . .	1
DRAINAGE BASIN AND DOWNSTREAM HAZARD ZONE . . . . .	1A
PLAN AND ELEVATION OF DAM . . . . .	2
MAXIMUM SECTION OF DAM AND SPILLWAY PROFILE. . . . .	3
GEOLOGIC MAP . . . . .	4-5
SEISMIC ZONE MAP . . . . .	6

APPENDICES

APPENDIX A	-	PHOTOGRAPHS
APPENDIX B	-	HYDROLOGIC AND HYDRAULIC COMPUTATIONS



PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

SMITH LAKE DAM, Missouri Inv. No. 11124

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

The Dam Inspection Act, Public Law 92-367 of August, 1972, authorizes the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspections. Inspection for Smith Lake Dam was carried out under Contract DACW 43-80-C-0094 between the Department of the Army, St. Louis District, Corps of Engineers, and the engineering firms of Consoer, Townsend & Associates, Ltd., and PRC Engineering Consultants, Inc. (A Joint Venture), of St. Louis, Missouri.

b. Purpose of Inspection

The visual inspection of Smith Lake Dam was made on July 8, 1980. The purpose of the inspection was to make a general assessment as to the structural integrity and operational adequacy of the dam embankment and its appurtenant structures.



c. Scope of Report

This report summarizes available pertinent data relating to the project, presents a summary of visual observations made during the field inspection, presents an assessment of hydrologic and hydraulic conditions at the site, and of the structural adequacy of the various project features and assesses the general condition of the dam with respect to safety.

Subsurface investigations, laboratory testing and detailed analyses were not within the scope of this study. No warranty as to the absolute safety of the project features is implied by the conclusions presented in this report.

It should be noted that in this report reference to left or right abutments is viewed as looking downstream. Where left abutment or left side of the dam is used in this report, this also refers to the west abutment or side, and right to the east abutment or side.

d. Evaluation Criteria

The inspection and evaluation of the dam is performed in accordance with the U.S. Army Corps of Engineers "Recommended Guidelines for Safety Inspection of Dams" and additional guidelines furnished by the St. Louis District office of the Corps of Engineers for Phase 1 Dam Inspection.



1.2

Description of the Project

a. Description of Dam and Appurtenances

The following description is based exclusively upon observations and measurements made during the visual inspection and conversations with Mr. Jerry Smith, the owner's representative. It should be noted that neither design drawings nor "as-built" drawings were available for the dam or appurtenant structures.

The dam is a compacted earthfill structure between earth abutments. Plate 2 shows a plan and elevation of the dam and Photos 1 through 3 show views of the dam. The top of dam varies in width along the axis of the dam. The top width is 35 feet for a distance of 150 feet to the right of the spillway while the remainder of the top of dam has been disguised by the dumping of fill material over the downstream face. Hence, the top of dam increases to 54-feet wide for the next 200 feet to the right and increases to 150 feet wide for the remaining 60 feet. The total length of the dam is 410 feet between the right abutment and the spillway. The top of dam is fairly level along the 35-foot wide section; the tops of the other two sections step up 2 feet and 5 feet, respectively, in relation to the 35-foot wide section. The minimum top of dam elevation at the 35-foot wide section is assumed to be at 581 feet above mean sea level (M.S.L.). The maximum structural height of the dam is 31 feet. The downstream slope of the embankment was measured as 1 vertical to 1.5 horizontal (1V on 1.5H) along most of the dam. The upstream slope of the embankment was measured as 1V on 2.25H from the crest to the water surface. No riprap was placed on the upstream slope.



There is only one spillway for this dam. The spillway is an earthcut, uncontrolled, open channel and is cut into the left abutment of the dam. The spillway is trapezoidal in shape with a top width of 25 feet, a bottom width of 10 feet and side slopes of approximately 1V on 2H (see plate 2). The crest of the spillway is 4 feet below the minimum top of dam. Flows through the spillway are directed away from the embankment by a training berm which extends at a right angle to the embankment for a distance of 250 feet downstream. The training berm is located on the right side of the spillway channel. The spillway channel slopes at about a 1 percent grade. At the downstream end of the channel, the channel makes a 90° bend in order to connect to the natural downstream channel.

No low level outlets or outlet works were provided for this dam.

b. Location

Smith Lake Dam is located in Pike County in the State of Missouri, and crosses an unnamed tributary of Noix Creek. The City of Louisiana is about one mile to the northwest. The Smith Lake Dam location on the 7.5 minute series of the U.S. Geological Survey maps is found in Section 20 of Township 54 North, Range 1 West, of the Louisiana, Missouri-Illinois Quadrangle Sheet.



c. Size Classification

The impoundment of Smith Lake Dam is 49 acre-feet, and the height is within the 25 to 40 foot range. Therefore, the size is determined to fall within the "small" category, according to the "Recommended Guidelines for Safety Inspection of Dams" by the U.S. Department of the Army, Office of the Chief Engineer.

d. Hazard Classification

The dam has been classified as having a "high" hazard potential in the National Inventory of Dams, on the basis that in the event of failure of the dam or its appurtenances, excessive damage could occur to downstream property, together with the possibility of the loss of life. Our findings concur with this classification. Within the estimated damage zone, extending half a mile downstream of the dam, are nine dwellings, two trailers, a railroad bridge and a State highway (Hwy 79).

e. Ownership

Smith Lake Dam is owned privately by Wayne B. Smith, Inc. The mailing address is as follows: Highway 79, Louisiana, Missouri 63553.

f. Purpose of Dam

Smith Lake Dam was constructed originally by a Cement Plant owner as a water source for his plant operations. At present, the lake is used only for recreation.



g. Design and Construction History

According to Mr. Jerry Smith, the dam was built in 1903 with horse drawn wooden scrapers. Under the present owner, the dam was partially rebuilt in 1963 and enlarged to its present size. No design drawings or calculations were available for either the original construction or the reconstruction in 1963.

h. Normal Operational Procedures

Normal procedure is to allow the lake to remain as full as possible with the water level being controlled by rainfall, runoff, evaporation and the elevation of the spillway crest.



1.3      Pertinent Data

a.    Drainage Area (square miles):. . . . . 0.07

b.    Discharge at Damsite

Estimated experienced maximum flood (cfs):. . . . . 70

Estimated ungated spillway capacity with  
reservoir at top of dam elevation (cfs):. . . . . 393

c.    Elevation (Feet above M.S.L.)

Top of dam (minimum):\* . . . . . 581

Spillway crest:. . . . . 577

Normal Pool: . . . . . 577

Maximum Experienced Pool:. . . . . 578.5

Observed Pool: . . . . . 575.5

d.    Reservoir

Length of pool with water surface  
at top of dam elevation (feet):. . . . . 750

e.    Storage (Acre-Feet)

Top of dam (minimum):. . . . . 49

Spillway crest:. . . . . 33

Normal Pool: . . . . . 33

Maximum Experienced Pool:. . . . . 39

Observed Pool: . . . . . 29

f.    Reservoir Surfaces (Acres)

Top of dam (minimum):. . . . . 4.5

Spillway crest:. . . . . 3.5

Normal Pool: . . . . . 3.5

Maximum Experienced Pool:. . . . . 3.8

Observed Pool: . . . . . 3.3



g. Dam

Type: . . . . .	Earthfill
Length: . . . . .	465 feet
Structural Height: . . . . .	31 feet
Hydraulic Height: . . . . .	31 feet**
Top width: . . . . .	Varies from 35 to 150 feet
Side slopes:	
Downstream . . . . .	1V on 1.5H
Upstream . . . . .	1V on 2.25H (Above the water surface)
Zoning: . . . . .	Unknown
Impervious core: . . . . .	Unknown
Cutoff: . . . . .	Unknown
Grout curtain: . . . . .	Unknown
Freeboard above normal reservoir level: . . . ; . . . . .	4 feet (Minimum)
Volume: . . . . .	42,000 cu.yds. (Estimated)

i. Spillway

```

Type: . . . . . Earthcut channel, uncontrolled
Length of crest: . . . . . 10 feet
Crest Elevation (feet above MSL): . . . 577

```

j. Regulating Outlets. . . None

\* The elevation of top of dam was assumed from the U.S.G.S. Louisiana, Missouri-Illinois Quadrangle topographic map. The elevation of other features of the dam were obtained by using this elevation and field measurements.



\*\* The hydraulic height of the dam is the vertical distance from the lowest point on the downstream toe to the top of dam or the maximum water surface, if below the top of dam.



## SECTION 2: ENGINEERING DATA

### 2.1 Design

No engineering plans, specifications, or "as-built" drawings were available for Smith Lake Dam. It is doubtful if any design was performed for the original construction in 1903 or the reconstruction in 1963.

### 2.2 Construction

No documented data is available concerning the construction of the dam and appurtenant structures, however, information was obtained from Mr. Jerry Smith concerning the reconstruction of the dam. Mr. Smith stated that the compaction was achieved by activity of the earth moving equipment across the dam. The material used for the embankment was a clay mixed with gravel which was taken from the area to the right of the dam.

### 2.3 Operation

No operational records are available for Smith Lake Dam.

### 2.4 Evaluation

#### a. Availability

The availability of engineering data is poor and consists only of State Geological Maps, a general soil maps of the state of Missouri published by the Soil Conservation Service, and U.S.G.S. Quadrangle sheets. In addition, no



pertinent data were available for review of hydrology, spillway capacity or flood routing through the reservoir. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available.

b. Adequacy

The lack of engineering data did not allow for a definitive review and evaluation. Therefore, the adequacy of this dam could not be assessed from the standpoint of reviewing and evaluating design, operation, and construction data, but is based primarily on visual inspection, past performance and present condition of the dam, and sound engineering judgement.

Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading condition and made a matter of record.

c. Validity

No valid engineering data were available.



### SECTION 3: VISUAL INSPECTION

#### 3.1 Findings

##### a. General

A visual inspection of the Smith Lake Dam was made on July 8, 1980. The following persons were present during the inspection:

<u>Name</u>	<u>Affiliation</u>	<u>Disciplines</u>
Dr. M.A. Samad	PRC Engineering Consultants, Inc.	Project Engineer, Hydraulics and Hydrology
Mark Haynes, P.E.	PRC Engineering Consultants, Inc.	Civil and Mechanical
Razi Quraishi, R.P.G.	PRC Engineering Consultants, Inc.	Geology
Zoran Batchko	PRC Engineering Consultants, Inc.	Soils
Kevin J. Blume	Consoer, Townsend & Assoc., Ltd.	Civil and Structural

Jerry Smith                      Owner's Representative

Specific observations are discussed below.



b. Dam

Only the upstream face of the dam has a vegetative cover which adequately protects the embankment material against surface runoff erosion (see photo 1). The upstream face is not protected by riprap, however, because of accumulated debris and the high water level, it was not possible to evaluate the extent of wave erosion, if any. There were a significant number of trees and large bushes observed on the upstream face of the dam. No cracks, bulges or depressions indicative of an instability of the slope were apparent.

The downstream embankment slope is generally unprotected by any vegetation (see Photo 3). Erosion gullies up to 6 feet deep and 3 feet wide were observed at several locations across the downstream slope (see Photo 4). Smaller erosion gullies on the order of about 1 foot deep were more frequent. The left 1/3 of the embankment slope adjacent to the spillway channel has medium sized trees growing on it. Some small rodent holes were observed on the slope. No cracks, bulges or depressions indicative of an instability of the slope were apparent.

The top of dam is generally irregular in shape and profile with a sparse vegetation cover (see Photo 2). The irregularity of the top of dam appears to be due to the practice of dumping materials on the top of dam and the downstream slope and not to an instability of the embankment. The vegetation growing on the crest is typically large weeds and a few small trees. Large shrinkage cracks on the order of 1/2 inch wide, up to 6 feet long, and 8 to 12 inches deep were observed over the major portion of the embankment crest and downstream face. According to the owner, the dam has never been overtopped and no evidence indicating the contrary was



observed.

There is no evidence of seepage or leakage through the embankment or foundation, however, several localized wet spots were encountered beyond the toe of the dam in the densely vegetated downstream area. It was undetermined whether these wet areas were due to seepage through the foundation or attributed to the recent heavy rains that occurred several days prior to our site inspection. No measurable flow was observed.

No signs of present instability were seen on the embankment or in the foundation. It should be kept in mind though, that periodic dumping on the downstream face from the owner's quarry operation could be masking an instability problem if one does exist. A portion of the dam, however, was reconstructed in the early 1960's due to a failure of the dam.

The left abutment is steeply sloped upward from the top of the dam. The right abutment is level for approximately 50 feet to the right of the dam, which is the access road to the dam, and then slopes moderately upward. The right abutment area directly east of the dam was used at one time as a rock quarry (see Photo 9). No instabilities, seepage or erosion were observed on either abutment.

#### c. Project Geology and Soils

##### (1) Project Geology

The damsite is located on an unnamed tributary of Noix Creek in the Dissected Till Plains Section of the Central Lowland Physiographic Province. Loess-mantled Kansas drift covers the surface of most of the Dissected Till Plains



Section. This section is distinguished from the Young Drift Section to the north and from the Till Plains on the east by the stage it has reached in the post-glacial erosion cycle. Broadly generalized, this section is a nearly flat till plain submature to mature in its erosion cycle.

The topography at the damsite is hilly with V- to U-shaped valleys. Elevation of the ground surface ranges from 580 feet above M.S.L. at the damsite to 834 feet above M.S.L. approximately 1.2 miles southwest of the damsite. The reservoir slopes are in the range of  $10^{\circ}$  to  $25^{\circ}$  from the horizontal and appear to be stable. The area near the damsite is covered with slope wash of glacial-fluvial deposits and loess.

The regional bedrock geology beneath the glacial outwash deposit in the damsite area as shown on the Geologic Map of Missouri (1979), (see Plate 4), consists of Pennsylvanian Marmaton-Cherokee Group (cyclic deposits of shale, limestone, and sandstone), Mississippian age Burlington Limestone, Mississippian Chouteau Group, Devonian Louisiana Formation, Silurian Bowling Green Limestone, and Ordovician rocks consisting of Maquoketa Shale, Kimmswick Limestone, Decorah Formation and St. Peter Sandstone.

The predominant bedrock in the site vicinity underlying the glacial-fluvial deposits are the Mississippian Burlington Limestone and Mississippian Chouteau Group of rocks consisting of interbedded limestones, cherty limestones, and siltstones. The inlet and outlet areas of the unnamed tributary of the Noix Creek contains Quaternary alluvium. An outcrop of horizontally bedded Mississippian Burlington Limestone (slightly weathered, brownish gray, very hard, cherty limestone), is exposed in a hill cut east of the right abutment (see Photos 9 and 10).



No faults have been identified in the vicinity of the damsite. The closest trace of a fault to the damsite is the Cap Au Gres faulted flexure nearly 18 miles south of the site. The Cap Au Gres faulted flexure had its last movement in post-Pennsylvanian, pre-Pleistocene time. Thus, the fault has no effect on the dam.

Smith Lake Dam consists of a homogeneous earthfill embankment and a spillway located at the left abutment. Based on the visual inspection and conversations with Mr. Jerry Smith, the embankment probably rests on the Mississippian Burlington Limestone bedrock. The spillway was cut into the glacial-fluvial deposits consisting of greenish yellow to brown, clayey silt. A localized slide scar was observed at the reservoir rim near the left abutment. This scar appears to have no detrimental effect on the stability of the reservoir bank.

## (2) Project Soils

According to the "Missouri General Soil Map and Soil Association Descriptions" published by the Soil Conservation Service, the materials in the general area of the dam belong to the soil series of Menfro-Winfield-Lindley in the Central Mississippi Valley Wooded Slopes family. The soils were basically formed from loess and glacial till. The permeability of these soils ranges from moderate to moderately slow. Field observations indicate that the moderately to high erodible Lindley type soils were used to construct the embankment. Overtopping of the dam would increase the potential for failure of the embankment due to erosion of the dam.



The material removed from the embankment was a brown and tan, sandy clay with traces of fine gravel. Based upon the Unified Soil Classification System, the soil would probably be classified as a CL. This soil type generally has the following characteristics: semipervious to impervious with a coefficient of permeability less than 100 feet per year, medium shear strength, and an intermediate resistance to piping.

d. Appurtenant Structures

(1) Spillway

The spillway channel was found obstructed with trees and bushes (see Photos 5 and 6). No erosion or instabilities of the side slopes of the channel were observed in the channel near the embankment, however, approximately 150 feet downstream of the embankment, considerable erosion has occurred in the channel and at the toe of the training berm. The erosional scarp extended across the entire width of the channel and was observed to be up to 7 feet deep. A comprehensive inspection of the spillway was hampered due to the heavy growth of vegetation in the spillway channel.

(2) Outlet Works

There are no regulated low level outlets or outlet works provided for this dam.



e. Reservoir Area

The reservoir water surface elevation at the time of inspection was approximately 575.5 feet above M.S.L.

The surface area of the reservoir at the normal pool elevation is about 3.5 acres. The reservoir rim area is generally heavily wooded (see Photo 8). The left side of the reservoir is moderately to steeply sloping with trees and woods extending to the rim of the reservoir. The right side of the reservoir is bounded by an access road beyond which lies moderately sloping hills. The upstream and downstream valleys are gently sloping and heavily wooded, also. There was no apparent evidence of instability in the reservoir rim area except for the localized slide scar mentioned in Section 3.1.c(1). There are no houses built in close proximity to the reservoir.

f. Downstream Channel

The downstream channel, which carries flows from the spillway, is overgrown with tall vegetation and is also obstructed by trees (see Photo 7). The channel varies in width from 20 to 50 feet and has side slopes of 1V to 1H. The channel is about 6 to 10 feet deep. Minor erosion was observed in the channel. The heavy growth of vegetation on the channel will affect the hydraulic efficiency of the channel.

3.2 Evaluation

The visual inspection uncovered nothing of a consequential nature which would require immediate remedial action. However, the following conditions were observed which could adversely affect the dam and the spillway.



1. The erosion of the downstream face does not affect the structural stability of the dam in its present condition, however, if the condition was to go unchecked, the condition could only worsen and jeopardize the safety of the dam.

2. It is recommended that trees and bushes be prevented from growing on the dam embankments. Depending upon the extent of the root system, the tree roots present possible paths for piping through the embankment which could endanger the safety of the dam. The root systems can also do damage to the embankment from being uprooted by a storm.

3. The rodent activity observed on the embankment could jeopardize the safety of the dam. The holes created by the animals make avenues for possible piping.

4. The source of the wet areas downstream of the embankment was unknown. Nevertheless, if the wet areas are due to seepage through the foundation of the dam, the stability of the dam could be in jeopardy. Seepage can transport soil particles which could cause piping of the foundation material. This could lead to an eventual failure of the embankment.

5. The upstream slope has no riprap protection, however, the extent of damage to the slope due to wave action, if any, is unknown.

6. The top of dam and the downstream slope are not adequately protected from surface runoff erosion which poses a potential danger to the safety of the dam.



7. Loose dumping of quarry spoils onto the downstream face is not a recommended practice. If continued, this practice could conceal serious problems, such as the 6 foot deep erosion gullies or the rodent activity, allowing them to go undetected.

8. The fractures and cracking on the crest and downstream face of the dam could conceivably become progressively worse due to freeze-thaw cycles and surface runoff erosion in the future if left in the "as is" condition. Nevertheless, they do not appear to pose a threat to the stability of the dam in their present condition nor are they indicative of an instability of the embankment.

9. The obstruction of the trees and bushes in the spillway does affect the hydraulic capability of the spillway and endangers the safety of the dam. The obstruction restricts the flow of water through the spillway, thus increasing the potential of overtopping the dam. This condition, if allowed to continue, can only worsen and further jeopardize the safety of the dam.

10. The erosion in the spillway channel does affect the stability of the channel and training berm. Nevertheless, it does not have an adverse effect on the safety of the dam and does not affect the operation of the spillway in its present condition.



## SECTION 4: OPERATIONAL PROCEDURES

### 4.1 Procedures

Smith Lake Dam is now used for recreational purposes and there are no methods or procedures that are followed for its operation. The water level is controlled by rainfall, runoff, evaporation, and the elevation of the spillway crest.

### 4.2 Maintenance of Dam

There is no program of maintenance for this dam, according to Mr. Jerry Smith. Mr. Smith also informed the inspection team that rock quarry spoils are periodically dumped on the downstream slope. There is an abundance of trees growing on both the upstream and downstream slopes and the top of dam.

### 4.3 Maintenance of Operating Facilities

There are no operating facilities at the damsite.

### 4.4 Description of Any Warning System in Effect

The inspection team is not aware of any warning system in use at the damsite.



4.5

Evaluation

The maintenance at Smith Lake Dam is poor. The remedial measures described in Section 7 should be undertaken to improve the condition of the dam.



## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

#### a. Design Data

No hydrologic and hydraulic design data is available for Smith Lake Dam. The sizes of physical features utilized to develop the stage-outflow relation for the spillway and overtopping of the dam were prepared from field notes and sketches prepared during the field inspection. The reservoir elevation-capacity data were based on the U.S.G.S. Louisiana, Missouri-Illinois Quadrangle topographic map (7.5 minute series). The spillway and overtop release rates and the reservoir elevation capacity data are presented in Appendix B.

The hydrologic soil group of the watershed of Smith Lake Dam was determined from information available in the U.S.D.A. Soil Conservation Service publication "Missouri General Soil Map and Soil Association Descriptions", 1979. The Probable Maximum Precipitation (PMP) used to determine the Probable Maximum Flood (PMF) was determined by using the U.S. Weather Bureau publication, "Hydrometeorological Report No. 33" (April 1956). The 100-year flood was derived from 100-year rainfall of Hannibal, Missouri.



b. Experience Data

It is believed that records of reservoir stage or spillway discharge are not maintained for this site. However, according to the owner, the maximum reservoir level was about 1-1/2 feet above the crest of the spillway.

c. Visual Observations

Observations made of the spillway during the visual inspection are discussed in Section 3.1d and evaluated in Section 3.2.

d. Overtopping Potential

Only the Probable Maximum Flood when routed through the reservoir, resulted in overtopping of the dam. The inflows for the PMF and one-half of the PMF are 1,182 cfs and 591 cfs, respectively. The peak outflow discharges for the PMF and one-half of the PMF are 890 and 243 cfs, respectively. The maximum capacity of the spillway just before overtopping the dam is 393 cfs. The PMF overtopped the dam by 0.75 feet. The total duration of overflow over the dam is 0.42 hours during the occurrence of the PMF. The spillway/reservoir system of Smith Lake Dam is capable of accommodating a flood equal to approximately 65 percent of the PMF just before overtopping the dam. The reservoir/spillway system of Smith Lake Dam will accommodate the one-percent chance flood without overtopping the dam. The surface soils on the embankment appear to be sandy clay and the soils on the spillway appear to be clayey silt. The maximum velocity of flow in the spillway during PMF will be about 6.5 ft/sec. The spillway channel may be subject to erosion due to high velocity of flow during the PMF. The dam may also be susceptible to erosion due to high velocity of



flow on its downstream slope, due to overtopping of the dam during the PMF.

The failure of the dam could cause extensive damage to the property downstream of the dam and possible loss of life. The estimated damage zone extends approximately half a mile downstream of the dam. Within the damage zone are nine dwellings, two trailers, a railroad bridge, and a State highway (Hwy 79).



## SECTION 6: STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

#### a. Visual Observations

There were no major signs of settlement or distress observed on the embankment or foundation during the visual inspection. However, some items which could affect the stability of the dam if not attended to within a reasonable period of time were observed on the embankment which includes the rodent holes, the erosion gullies up to 6 feet deep, the 1 foot deep shrinkage cracks, and the loosely dumped fill. The wet spots observed below the downstream toe of the dam may be indicative of seepage beneath the dam, however, no wet spots were observed on the embankment. The loosely dumped fill on the right portion of the downstream face is at a very steep angle. Furthermore, because the fill is uncompacted, further erosion due to surface runoff is expected to be severe, thus adding to the potential instability. In the absence of seepage and stability analyses, no quantitative evaluation of the structural stability can be made.

The spillway appeared to be structurally stable on the day of the inspection except for the severe erosion at the downstream end of the spillway channel. The erosion does not affect the stability of the dam in its present condition.



b. Design and Construction Data

Design computations pertaining to the embankment were not available during the report preparation phase. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available. No embankment or foundation soil parameters were available for carrying out a conventional stability analysis on the embankment. No construction data or specifications relating to the degree of embankment compaction were available for use in a stability analysis.

c. Operating Records

No operating records were available relating to the dam or appurtenant structures. The water level on the day of the visual inspection was approximately 1-1/2 feet below the spillway crest. The normal water level is at the spillway crest. According to Mr. Jerry Smith, the water level fluctuates approximately four feet during the year.

d. Post Construction Changes

The only post construction changes known to exist which could affect the structural stability of the dam are the reconstruction of the embankment in 1963 and the practice of loosely dumping of materials on the downstream slope. It is unknown what effect the reconstruction of the embankment had on the overall structural stability of the dam due to the fact that no engineering data concerning this change exists. The loosely dumping of materials on the downstream slope, even though it is not a recommended practice, could have a positive effect on the structural stability of the dam if proper methods of placing the material are employed.



e. Seismic Stability

The dam is located in Seismic Zone 2, as defined in "Recommended Guidelines For Safety Inspection of Dams" prepared by the Corps of Engineers, and will not require a seismic stability analysis. An earthquake of the magnitude which would be expected in Seismic Zone 2 should not cause significant distress to a well designed and constructed earth dam. Available literature indicates that no active faults exist in the vicinity of the damsite.



## SECTION 7: ASSESSMENT/REMEDIAL MEASURES

### 7.1 Dam Assessment

The assessment of the general condition of the dam is based upon available data and visual inspection. Detailed investigations, testing and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

It should be realized that the reported condition of the dam is based upon observations of field conditions at the time of inspection along with data available to the inspection team.

It is also important to note that the condition of a dam depends upon numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be assurance that an unsafe condition could be detected.

#### a. Safety

The spillway capacity of Smith Lake Dam is found to be "Inadequate". The spillway/reservoir system will accommodate approximately 65 percent of the PMF without overtopping the dam. The surface soils on the embankment appear to be sandy clay and the soils on the spillway appear to be clayey silt. The dam is overtopped by 0.42 feet during the occurrence of the PMF. The maximum velocity of flow in the spill-



way during PMF will be about 6.5 ft/sec. The spillway channel may be subject to erosion due to high velocity of flow during the PMF. The dam may also be susceptible to erosion due to high velocity of flow on its downstream slope, due to overtopping of the dam during the PMF.

A quantitative evaluation of the safety of the embankment could not be made in view of the absence of seepage and stability analyses. The present embankment and appurtenant structures, however, reportedly have performed satisfactorily since the 1963 reconstruction; there have been no failures or evidence of instability. The dam, reportedly, has never been overtopped and no evidence indicating the contrary was observed. The safety of the dam can be improved if the deficiencies described in Sections 3 and 6.1a are properly corrected as described in Section 7.2.

b. Adequacy of Information

The conclusions presented in this report are based upon field measurement, past performance, and the present condition of the dam. Information on the design hydrology, hydraulic design, or the operation and maintenance of the dam were not available. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.

c. Urgency

The remedial measures recommended in Paragraph 7.2 should be accomplished within a reasonable period of time, and the item recommended in paragraph 7.2a should be pursued on a high priority basis.



d. Necessity for Phase II Inspection

Based upon results of the Phase I inspection, a Phase II inspection is not felt to be necessary.

7.2 Remedial Measures

a. Alternatives

One of the following mitigation measures should be undertaken under the guidance of a professional engineer experienced in design and construction of earth dams to avoid severe consequences of dam failure from overtopping.

1. Increase the spillway capacity to pass the Probable Maximum Flood without overtopping the dam.
2. Increase the height of the dam enough to pass the PMF without overtopping the dam; an investigation should also be done that includes studying the effects on the structural stability of the existing embankment. The overtopping depth during the occurrence of the PMF, stated in Section 5.1d, is not the required or recommended increase in the height of the dam.
3. A combination of 1 and 2 above.
4. Provide highly reliable flood warning system (generally does not prevent damage but avoids loss of life).



b. O & M Procedures

1. The erosion gullies on the downstream slope should be properly backfilled and the entire slope adequately protected from further erosion.
2. All of the trees should be removed from the embankment. Removal of large trees should be under the guidance of an engineer experienced in the design and construction of earth dams. Indiscriminate clearing could jeopardize the safety of the dam.
3. The extent of damage done to the embankment by burrowing animals, if any, should be determined and make corrective repairs as required. All burrowing animals should be eliminated from the embankment and their burrows properly backfilled and compacted.
4. The wet areas downstream of the toe of the embankment should be monitored to determine the source of the moisture and to ensure the safety of the dam. If the condition is indeed due to seepage, the area should be monitored to detect any changes in location, turbidity and quantity of water. Any changes should be reported and investigated further.
5. The upstream slope should be cleared of all unwanted vegetation, including the trees as mentioned above; the slope properly repaired, if required, and adequately protected against wave action and surface runoff.
6. The top of dam should be adequately protected from surface runoff erosion.




7. The practice of loosely dumping quarry spoils onto the downstream face and top of dam must be discontinued. This practice, if continued, will severely hinder the comprehensive inspection of the dam by concealing possible warning signs which would be otherwise observable.
8. The cracks on the top of dam and downstream slope should be properly repaired and the embankment monitored for further cracking to ensure the safety of the dam.
9. The obstruction created by trees and bushes in the spillway channel should be removed and adequate protective cover retained in the channel.
10. The severe erosion in the spillway channel should be monitored to ensure that it does not jeopardize the stability of the dam and repairs made when deemed necessary.
11. Seepage and stability analyses should be performed by a professional engineer experienced in the design and construction of earth dams.
12. The owner should initiate the following programs:
  - (a) Periodic inspection of the dam by a professional engineer experienced in the design and construction of earth dams.
  - (b) Set up a maintenance schedule and log all visits to the dam for operation, repairs and maintenance.




PLATES










QUADRANGLE LOCATION

LOUISIANA QUADRANGLE

SCALE 1:24,000




CONTOUR INTERVAL 5 AND 20 FEET  
DATUM IS MEAN SEA LEVEL

DRAINAGE BOUNDARY - - - - -

SMITH LAKE DAM - MO. 11124  
DRAINAGE BASIN AND  
DOWNSTREAM HAZARD ZONE




SCALE:  
HORIZ. 1" = 60'  
VERT. 1" = 5'




SMITH LAKE DAM (MO. 11124)  
PLAN AND ELEVATION





MAXIMUM SECTION




SECTION A-A  
(SPILLWAY PROFILE)

SCALE:  
HORIZ. 1" = 60'  
VERT. 1" = 5'

SMITH LAKE DAM (MO. 11124)  
MAXIMUM SECTION OF EMBANKMENT  
AND SPILLWAY PROFILE





⊕ LOCATION OF DAM

NOTE: LEGEND OF THIS DAM IS ON PLATE 5

REFERENCE:

GEOLOGIC MAP OF MISSOURI  
DEPARTMENT OF NATURAL RESOURCES  
MISSOURI GEOLOGICAL SURVEY  
KENNETH H. ANDERSON, 1979

REGIONAL GEOLOGICAL MAP  
OF  
SMITH LAKE DAM



LEGEND

<u>PERIOD</u>	<u>SYMBOL</u>	<u>DESCRIPTION</u>
QUATERNARY	Qal	ALLUVIUM: SAND, SILT, GRAVEL
PENNSYLVANIAN	Pm	MARMATON GROUP: CYCLIC DEPOSITS OF SHALE, LIMESTONE AND SANDSTONE
	Pcc	CHEROKEE GROUP: CYCLIC DEPOSITS OF SHALE, LIMESTONE AND SANDSTONE
MISSISSIPPIAN	Mo	KEOKUK - BURLINGTON FORMATION: CHERTY GRAYISH BROWN SANDY LIMESTONE
	Mk	CHOUTEAU GROUP: HANNIBAL AND BACHELOR FORMATION (SANDSTONE, SHALE, CHERTY LIMESTONE, DOLOMITE)
DEVONIAN	D	LOUISIANA FORMATION: (INTERBEDDED LIMESTONE, CHERTY LIMESTONE AND SILTSTONE)
SILURIAN	S	BOWLING GREEN LIMESTONE
ORDOVICIAN	Ou	NOIX LIMESTONE
	Omk	MAQUOKETA SHALE, KIMMSWICK LIMESTONE
	Odp	DECORAH FORMATION: GREEN TO GRAY CALCAREOUS SHALE WITH THIN FOSSILIFEROUS LIMESTONE
	Osp	ST PETER SANDSTONE



APPENDIX A

PHOTOGRAPHS






PHOTO INDEX  
FOR  
SMITH LAKE DAM



## Smith Lake Dam

### Photographs

- Photo 1 - View of the upstream slope from the right abutment showing the growth of trees and vegetation.
- Photo 2 - View of the top of dam showing irregular shape and sparse vegetative cover.
- Photo 3 - View of the downstream slope showing sparse vegetative cover and trees.
- Photo 4 - Close-up view of erosional gully on the downstream slope.
- Photo 5 - View of the spillway taken from the spillway channel looking back toward the reservoir and showing the obstruction of trees and bushes.
- Photo 6 - View of the spillway channel also showing the obstruction of trees and bushes.
- Photo 7 - View of the downstream channel near the point where the spillway channel intersects the downstream channel.
- Photo 8 - View of the reservoir and rim.
- Photo 9 - View of the rock quarry excavation on the right abutment area adjacent to the dam.
- Photo 10 - Close-up view of the exposed Burlington Limestone in the rock quarry.



Photo 11 - View of a dwelling approximately 0.5 miles downstream of the dam with the downstream channel in the background.

Photo 12 - View of a dwelling approximately 0.5 miles downstream of the dam looking across the downstream channel.



Smith Lake Dam




Photo 1



Photo 2



Smith Lake Dam



Photo 3



Photo 4



Smith Lake Dam



Photo 5




Photo 6



Smith Lake Dam



Photo 7



Photo 8



Smith Lake Dam



Photo 9



Photo 10



Smith Lake Dam



Photo 11



Photo 12



APPENDIX B

HYDROLOGIC AND HYDRAULIC COMPUTATIONS



## SMITH LAKE DAM

### HYDROLOGIC AND HYDRAULIC DATA, ASSUMPTIONS AND METHODOLOGY

1. SCS Unit Hydrograph and HEC-1DB are used to develop the inflow hydrographs, and the hydrologic inputs are as follows:
  - (a) Twenty-four hour probable maximum precipitation from Hydro-meteorological Report No. 33, 24-hour 100-year rainfall of Hannibal, Missouri.
  - (b) Drainage area = 45 acres
  - (c) Lag time = 0.053 hour
  - (d) Hydrologic Soil Group:  
Soil Group "C"
  - (e) Runoff curve number:  
CN = 77 for AMC II and CN = 89 for AMC III
2. Spillway release rates are based on open channel flow assuming Manning's  $n = 0.04$ . Flow rates over the dam are based on broad crested weir equation  $Q = CLH^{3/2}$ .
3. Floods are routed through Smith Lake to determined the capability of its spillway.



## DAM SAFETY INSPECTION - MISSOURI


SHEET NO. 1 OF 2

SMITH LAKE DAM - (MO 11124)

JOB NO. 1263

### SPILLWAY AND OVERTOP RATING CURVE

BY D.C DATE 7/17/80



$X$	$Y_1$	$A_1$	$T_1$	$V_1$	$\frac{V_1^2}{2g}$	$Q_{1/4}^2 A_1$	$\omega s, E, L^3$ $Y_1 + \frac{V_1^2}{2g}$ 1577	$H_1$	$L_1$	$C_1$	$Q_1 c_1 u_1^{3/4}$	$H_2$	$C_2$	$L_2$	$Q_2 c_2 u_2^{3/4}$	$H_3$	$L_3$	$C_3$	$Q_3 c_3 u_3^{3/4}$	$H_4$	$L_4$
1.83	24.58	16.86	4.67	.26	100	579.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
2.63	39.23	19.86	5.10	.40	200	580.03	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3.23	51.84	22.11	5.79	.52	300	580.75	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3.72	63.21	23.96	6.33	.62	400	581.34	.34	150'	3.00	89.09	-	-	-	-	-	-	-	-	-	.34	50'
4.14	73.49	25.0	6.80	.72	500	581.86	.86	150	3.03	86.28	-	-	-	-	-	-	-	-	-	.86	50
4.85	91.21	25.0	7.67	.91	700	582.76	1.76	150	3.04	106.597	-	-	-	-	-	-	-	-	-	1.76	50
5.17	99.22	25.0	8.06	1.01	800	583.18	2.18	150	3.05	147.105	.18	296	200'	45.21	-	-	-	-	-	2.18	50
5.81	115.22	25.0	8.68	1.17	1000	583.98	2.98	150	3.05	235.475	.98	303	200	588.82	-	-	-	-	-	2.98	50
6.97	144.6	25.0	8.71	1.46	1400	585.43	4.43	150	3.06	4276.49	2.43	305	200	2309.54	-	-	-	-	-	4.43	50

**B-2A**

OBTAIN FROM HEC-2. By assuming critical depth 250' downstream and using backwater program HEC-2 To obtain  $Y$  values. (See plate 3, under station 101ates, for spillway: file)



## PRC ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION - MISSOURI

SHEET NO. 2 OF 2

SMITH LAKE DAM - (MO 11124)

JOB NO. 1263

SPILLWAY AND OVERTOP RATING CURVE

BY DC DATE 7/17/90

$C_u$	$Q_u, Q_{4u}, \frac{1}{2} Q_u$	$H_u$	$Y_u = \frac{2}{3} \left( \frac{H_u + Y_u}{2} \right)$	$T_u$	$A_u$	$Q_u \sqrt{\frac{A_u}{T_u}}$	$Q_u^1, Q_u^2, Q_u^3$
300	29.70	.34	.27	.27	.037	.077	519
303	120.93	.86	.69	.69	.24	.79	985
304	355.32	1.76	1.41	1.41	.99	4.72	2126
305	490.35	2.18	1.74	1.74	1.52	8.06	2815
306	784.92	2.98	2.38	2.38	2.54	17.6	4746
306	1425.5	4.43	3.54	3.54	6.28	42.44	9459



HEC-2 INPUT AND SUMMARY TABLE







HEC2 RELEASE DATED NOV 76 UPDATED JULY 1979  
 ERROR CORR - P1002403  
 MODIFICATION - 000115053

NOTE- ASTERISK (\*) AT LEFT OF CROSS-SECTION NUMBER INDICATES MESSAGE IN SUMMARY OF ERRORS LIST

SPILLWAY RATING CURVE  
 SUMMARY PRINTOUT

SECTION	DEPTH	AREA	TOTWID	VCH	HW	Q	EG	10K-S	MOXNCH
1-000	1.55	16.65	14.79	6.01	.56	100.00	575.89	241.54	40.00
1-000	2.02	27.82	17.57	7.19	.80	200.00	576.82	218.61	40.00
1-000	2.55	37.40	19.08	7.94	.98	300.00	577.53	206.62	40.00
1-000	3.03	47.18	21.50	8.48	1.12	400.00	578.13	197.62	40.00
1-000	3.42	56.07	23.82	8.92	1.23	500.00	578.65	191.25	40.00
1-000	4.08	72.04	29.00	9.72	1.47	700.00	579.35	186.37	40.00
1-000	4.56	79.07	29.00	10.14	1.54	800.00	579.95	183.17	40.00
1-000	4.85	91.31	29.00	10.75	1.86	1000.00	580.71	185.77	40.00
1-000	5.77	114.36	25.60	12.24	2.33	1400.00	582.10	186.82	40.00
2-000	1.93	24.28	16.46	4.97	.26	100.00	579.09	77.84	40.00
2-000	2.63	39.23	19.86	5.10	.40	200.00	580.03	82.13	40.00
2-000	3.23	51.84	22.11	5.79	.58	300.00	580.75	85.87	40.00
2-000	4.14	63.21	23.96	6.33	.62	400.00	581.34	87.94	40.00
2-000	4.71	73.49	25.00	6.80	.72	500.00	581.60	89.48	40.00
2-000	5.17	90.22	25.60	7.67	.91	700.00	582.76	91.32	40.00
2-000	5.81	115.72	25.00	8.68	1.07	800.00	583.18	92.77	40.00
2-000	6.57	144.16	26.00	9.71	1.17	1000.00	583.98	93.23	40.00
2-000					1.24	1400.00	585.43	93.43	40.00

SUMMARY OF ERRORS

CAUTION	SECTION 1	1-000	PROFILE 1	CRITICAL	DEPTH ASSUMED
CAUTION	SECTION 2	1-000	PROFILE 2	CRITICAL	DEPTH ASSUMED
CAUTION	SECTION 3	1-000	PROFILE 3	CRITICAL	DEPTH ASSUMED
CAUTION	SECTION 4	1-000	PROFILE 4	CRITICAL	DEPTH ASSUMED
CAUTION	SECTION 5	1-000	PROFILE 5	CRITICAL	DEPTH ASSUMED
CAUTION	SECTION 6	1-000	PROFILE 6	CRITICAL	DEPTH ASSUMED
CAUTION	SECTION 7	1-000	PROFILE 7	CRITICAL	DEPTH ASSUMED
CAUTION	SECTION 8	1-000	PROFILE 8	CRITICAL	DEPTH ASSUMED
CAUTION	SECTION 9	1-000	PROFILE 9	CRITICAL	DEPTH ASSUMED



## PRC ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION - MISSOURI

SHEET NO. 1 OF 1

DAM NAME: Smith Lake Dam / ID NO.: 11124

JOB NO.

RESERVOIR ELEVATION - AREA DATA

BY C DATE 7/12

ELEV. (M.S.L.) (Ft.)	RESERVOIR SURFACE AREA (Acres)	REMARKS
555	0	Estimated Streambed
570	2.5	Interpolated
577	3.5	Spillway Crest
580	4.0	Measured on USGS Map
581	4.5	Top of Dam (Assumed elevation)
590	5.5	Interpolated
600	7.5	Measured on USGS Map



DAM SAFETY INSPECTION / MISSOURI

SHEET NO. 1 OF 1

DAM NAME: SMITH LAKE DAM

JOB NO. 1263

UNIT HYDROGRAPH PARAMETERS

BY D.C. DATE 7/15/80

- 1) DRAINAGE AREA,  $A = .071$  sq. mi. = (45 acres)
- 2) LENGTH OF STREAM,  $L = (.8 \times 2000' = 1600') = .303$  mi.
- 3) ELEVATION AT DRAINAGE DIVIDE ALONG THE LONGEST STREAM,  
 $H_1 = 761'$
- 4) ELEVATION OF RESERVOIR AT SPILLWAY CREST,  $H_2 = 577'$
- 5) ELEVATION OF CHANNEL BED AT  $0.85L$ ,  $E_{85} = 680'$
- 6) ELEVATION OF CHANNEL BED AT  $0.10L$ ,  $E_{10} = 578'$
- 7) AVERAGE SLOPE OF THE CHANNEL,  $S_{AVG} = (E_{85} - E_{10}) / 0.75L = .085$
- 8) TIME OF CONCENTRATION:

A) BY KIRPICH'S EQUATION,

$$t_c = [(11.9 \times L^3) / (H_1 - H_2)]^{0.385} = \left( \frac{11.9 \times .303^3}{761 - 577} \right)^{0.385} = .088 \text{ hr}$$

B) BY VELOCITY ESTIMATE,

$$\text{SLOPE} = 7.5\% \Rightarrow \text{AVG. VELOCITY} = 5 \text{ fps}$$

$$t_c = L / V = .089 \text{ hr}$$

USE  $t_c = .089$  hr.

$$9) \text{ LAG TIME, } t_L = 0.6 t_c = .0528 \text{ hr.}$$

$$10) \text{ UNIT DURATION, } D \leq t_L / 3 = .0176 \text{ hr.}$$

$$< 0.083 \text{ hr.}$$

USE  $D = .083$  hr.

$$11) \text{ TIME TO PEAK, } T_p = D/2 + t_L = .095 \text{ hr.}$$

12) PEAK DISCHARGE,

$$q_p = (484 \times A) / T_p = 365 \text{ cfs}$$



# PRC ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION


SHEET NO. 1 OF 1

SMITH LAKE DAM

JOB NO. 1263

STARTING WSEL FOR PMF ROUTING

BY D.C. DATE 7/17/80



I. WSEL = 577.1 at end of  $\frac{1}{2}$  PMF Routing

From WSEL  $\Rightarrow$  577.1 to 577

$$\Delta S = 34 - 33 = 1 \text{ ac-ft}$$

$$Q = 2.5 \text{ cfs}$$

$$t = 1 \text{ ac-ft} \times 43560 \frac{\text{ft}^2}{\text{ac}} \times \frac{1}{2.5 \text{ cfs}} \times \frac{1 \text{ day}}{86400 \text{ s}} = 0.2 \text{ days} < 3 \text{ days}$$

$\therefore$  Since water level returns to spillway crest in less than 3 days, start PMF routing when W.L. is at spillway crest.



\*\*\*\*\*  
FLOOD HYDROGRAPH PACKAGE (HEC-1)  
DAY SAFETY VERSION JULY 1978  
LAST MODIFICATION 26 FEB 79

**● ●**

1. DEMS

100

[illegible]

3 A3 P2/F A3

4 3 300

515

115

7111

3 4 0 201

LINEAL	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	

3 :  
Y I :  
INFU I

100

3

12 1

13 12

14 X

15  
15

ROUTE	17
ROUTE	16
ROUTE	15

7-11-67

1. *Chlorophyll a* (Chl a) and *Chlorophyll b* (Chl b) are the primary photosynthetic pigments in green plants. They are responsible for capturing light energy and converting it into chemical energy through the process of photosynthesis. Chl a is the most abundant pigment, while Chl b is present in smaller amounts. Both pigments are found in the chloroplasts of green plants.

# SYLLI

19 Y4 577 577

20 Y5 0

213A0

22 31 55  
22 31 55

21 18 577

11	→	3
11	→	3
11	→	3

18c 04

25 99

[illegible]

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
84

100

**B-10**



**JUL 07 1968**

WAY SAFELY INSPECTION. MISSOURI  
SMITH LAKE DAM (MO, 1112  
PME AND 120 PERCENT PMF &

009 SPECIFICATION  
1HR 1 MIN  
NWT LROP

MULTI-PLAN ANALYSES TO BE PERFORMED  
NPLAN=1 NRITC=2 LRTIC=1

SUB-AREA RUOFF COMPUTATION

INPUT, PRECIPITATION, INDEX, RAINFALL, AND UNIT HYDROGRAPH PARAMETERS

[illegible]

HYDROGRAPH DATA

PRECIP. DATA

21M 00.00 130.00 00.00

100

U. S. S. S. R.

1

177

# HYDROGRAPH

100

GRCSN3

81148/2)

100

10

1

1



MO,DA	HR,MIN	PERIOD	WAT.	LOSS	END-OF-PERIOD FLOW	NO,DA	HR,MIN	PERIOD	RAIN	EVCS	LOSS
1.01	0.0	1	0.0	0.00	0.0	1.01	12.13	154	12.0	12.0	12.0
1.01	0.0	2	0.0	0.00	0.0	1.01	12.40	152	20.0	20.0	20.0
1.01	0.0	3	0.0	0.00	0.0	1.01	12.45	153	20.0	20.0	20.0
1.01	0.0	4	0.0	0.00	0.0	1.01	12.50	154	20.0	20.0	20.0
1.01	0.0	5	0.0	0.00	0.0	1.01	12.55	155	20.0	20.0	20.0
1.01	0.0	6	0.0	0.00	0.0	1.01	13.00	156	20.0	20.0	20.0
1.01	0.0	7	0.0	0.00	0.0	1.01	13.05	157	22.0	22.0	22.0
1.01	0.0	8	0.0	0.00	0.0	1.01	13.10	158	25.0	25.0	25.0
1.01	0.0	9	0.0	0.00	0.0	1.01	13.15	159	25.0	25.0	25.0
1.01	0.0	10	0.0	0.00	0.0	1.01	13.20	160	25.0	25.0	25.0
1.01	0.0	11	0.0	0.00	0.0	1.01	13.25	161	25.0	25.0	25.0
1.01	0.0	12	0.0	0.00	0.0	1.01	13.30	162	25.0	25.0	25.0
1.01	0.0	13	0.0	0.00	0.0	1.01	13.35	163	25.0	25.0	25.0
1.01	0.0	14	0.0	0.00	0.0	1.01	13.40	164	25.0	25.0	25.0
1.01	0.0	15	0.0	0.00	0.0	1.01	13.45	165	25.0	25.0	25.0
1.01	0.0	16	0.0	0.00	0.0	1.01	13.50	166	25.0	25.0	25.0
1.01	0.0	17	0.0	0.00	0.0	1.01	13.55	167	25.0	25.0	25.0
1.01	0.0	18	0.0	0.00	0.0	1.01	14.00	168	25.0	25.0	25.0
1.01	0.0	19	0.0	0.00	0.0	1.01	14.05	169	31.0	31.0	31.0
1.01	0.0	20	0.0	0.00	0.0	1.01	14.10	170	31.0	31.0	31.0
1.01	0.0	21	0.0	0.00	0.0	1.01	14.15	171	31.0	31.0	31.0
1.01	0.0	22	0.0	0.00	0.0	1.01	14.20	172	31.0	31.0	31.0
1.01	0.0	23	0.0	0.00	0.0	1.01	14.25	173	31.0	31.0	31.0
1.01	0.0	24	0.0	0.00	0.0	1.01	14.30	174	31.0	31.0	31.0
1.01	0.0	25	0.0	0.00	0.0	1.01	14.35	175	31.0	31.0	31.0
1.01	0.0	26	0.0	0.00	0.0	1.01	14.40	176	31.0	31.0	31.0
1.01	0.0	27	0.0	0.00	0.0	1.01	14.45	177	31.0	31.0	31.0
1.01	0.0	28	0.0	0.00	0.0	1.01	14.50	178	31.0	31.0	31.0
1.01	0.0	29	0.0	0.00	0.0	1.01	14.55	179	31.0	31.0	31.0
1.01	0.0	30	0.0	0.00	0.0	1.01	15.00	180	31.0	31.0	31.0
1.01	0.0	31	0.0	0.00	0.0	1.01	15.05	181	31.0	31.0	31.0
1.01	0.0	32	0.0	0.00	0.0	1.01	15.10	182	31.0	31.0	31.0
1.01	0.0	33	0.0	0.00	0.0	1.01	15.15	183	31.0	31.0	31.0
1.01	0.0	34	0.0	0.00	0.0	1.01	15.20	184	31.0	31.0	31.0
1.01	0.0	35	0.0	0.00	0.0	1.01	15.25	185	31.0	31.0	31.0
1.01	0.0	36	0.0	0.00	0.0	1.01	15.30	186	31.0	31.0	31.0
1.01	0.0	37	0.0	0.00	0.0	1.01	15.35	187	31.0	31.0	31.0
1.01	0.0	38	0.0	0.00	0.0	1.01	15.40	188	31.0	31.0	31.0
1.01	0.0	39	0.0	0.00	0.0	1.01	15.45	189	31.0	31.0	31.0
1.01	0.0	40	0.0	0.00	0.0	1.01	15.50	190	31.0	31.0	31.0
1.01	0.0	41	0.0	0.00	0.0	1.01	15.55	191	31.0	31.0	31.0
1.01	0.0	42	0.0	0.00	0.0	1.01	16.00	192	31.0	31.0	31.0
1.01	0.0	43	0.0	0.00	0.0	1.01	16.05	193	31.0	31.0	31.0
1.01	0.0	44	0.0	0.00	0.0	1.01	16.10	194	31.0	31.0	31.0
1.01	0.0	45	0.0	0.00	0.0	1.01	16.15	195	31.0	31.0	31.0
1.01	0.0	46	0.0	0.00	0.0	1.01	16.20	196	31.0	31.0	31.0
1.01	0.0	47	0.0	0.00	0.0	1.01	16.25	197	31.0	31.0	31.0
1.01	0.0	48	0.0	0.00	0.0	1.01	16.30	198	31.0	31.0	31.0
1.01	0.0	49	0.0	0.00	0.0	1.01	16.35	199	31.0	31.0	31.0
1.01	0.0	50	0.0	0.00	0.0	1.01	16.40	200	31.0	31.0	31.0
1.01	0.0	51	0.0	0.00	0.0	1.01	16.45	201	31.0	31.0	31.0
1.01	0.0	52	0.0	0.00	0.0	1.01	16.50	202	31.0	31.0	31.0
1.01	0.0	53	0.0	0.00	0.0	1.01	16.55	203	31.0	31.0	31.0
1.01	0.0	54	0.0	0.00	0.0	1.01	17.00	204	31.0	31.0	31.0
1.01	0.0	55	0.0	0.00	0.0	1.01	17.05	205	31.0	31.0	31.0



[illegible]











HYDROGRAPH KOUING

ROUTE HYDROGRAPH THROUGH SMITH LAKE DAM (MO 11124)

ISTAD	ICOMP	RECON	TAPE	JULI	JPRI	INAME	ISTAGE	IAUTO
11124	1	0	0	0	0	1	0	0

QJLSS	CLOSS	AVG	IRIS ISAME	TOTI	IPMP	LSTR

INSTPS NSIOL LAG ANSKK STORA ISPHAT

[illegible]

200100	300000	517,000	905,000	2126,000
--------	--------	---------	---------	----------

30. 4. 5. 6. 7. 8.

[illegible][illegible]

0.0 0.0 0.0 0.0 0.0 0.0

UAM Data

TOPIC	CODE	LNPH	PARMID
58110	0.0	0.0	0.0

STATION 01124, PLAN 1: RATIO 1 -

END OF PEN 00. HYDROGRAPH ORDINATES  
OUTFLOW

100

100

100

[illegible]

**Abstract**

100



PLAN FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE FEET (SQUARE METERS)

OPERATION STATION PLAN RATIO 1 RATIO 2 RATIO APPLIED TO FLOWS  
 1.00 150

HYDROGRAPH AT 011124 11824 5910  
 1 334771 154731

ROUTED TO 011124 1 3904 2434  
 1 25.211 64031



10

RATIO OF PME	MAXIMUM RESERVOIR WATERLEVEL	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM CUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
1.00	581.75	175	52	890	.2	15.67	8.88
1.50	580.39	0.00	96	243	0.00	15.67	8.88



95, 0411-80/00/04.  
 , TIME 10.09.27.

DAM SAFETY INSPECTION MISSOURI  
SMITH LAKE DAM (MO 11124)  
PERCENT PMF

JOB SPECIFICATION

JOB SPECIFICATION									
NO	NHR	NMIN	IDAY	IHR	IMIN	IMEC	IPLY	IPRT	INSTAN
300	0	5	0	0	0	0	0	-1	0
			JOSEP	NW	LRQPT	TRACE			
		5	5	0	0	0			

## MULTI-PLAN ANALYSES TO BE PERFORMED

RILOS= .60 .65  
NPLAN= 1 NRILO= 1 LRILO= 1  
70 75

## SUB-AREA RUNOFF COMPUTATION

### INFLUENT PRECIPITATION INDEX, RATIOS, AND UNIT HYDROGRAPH PARAMETERS

DATE	TIME	ISTAT	ICOMP	IRECON	ITAPL	JPLT	JPR1	INAME	ISTAGE	IAUTO
1966	1	011124	0	0	0	0	0	0	1	0

HYDROGRAPH DATA							
DATE	TIME	SNAP	IRSOA	RAT10	ISNCH	ISANT	LOCAL
1966	1	01	0.00	1.00	0.000	0	0

PRECIP DATA

SPEC	PMS	N6	N12	N24	R48	H72	F96
0.00	24.50	100.00	120.00	150.00	0.00	0.00	0.00

LOSS DATA

LCS DATA										
LAUPT	STNKH	DLFKH	RYLOL	ERAIN	STNKS	RTIOK	STRTL	CASIL	ALSMX	RTIMP
0	0400	0000	1.00	0.00	0.00	1.00	1.00	-0.00	0.00	0.00

CURVE NO = -09.00 WEIERS = 1.00 EFFECT CN = 09.00

## UNIT HYDROGRAPH DATA

ICE 0.00 LAG= .05 "

REC'D: 10-11-68

[illegible][illegible]



SUM 3145 3034 100 1000  
 000117251 30.0 012000

ROUTING DATA

ROUTE HYDROGRAPH THROUGH SMITH LAKE DAM (NO. 11114)

HYDROGRAPH ROUTING

INLET TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD

OUTLET TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD TCMPCD

STAGE 577.00 579.00 581.00 583.00 585.00 587.00 589.00 591.00 593.00 595.00

FLOW 100.00 200.00 300.00 400.00 500.00 600.00 700.00 800.00 900.00 1000.00

SURFACE AREA 0.0 10.0 20.0 30.0 40.0 50.0 60.0 70.0 80.0 90.0

CAPACITY 0.0 10.0 20.0 30.0 40.0 50.0 60.0 70.0 80.0 90.0

ELEVATION 555.0 570.0 577.0 590.0 590.0 590.0 590.0 590.0 590.0 590.0

PEAK OUTFLOW IS 323. AT TIME 15.75 HOURS

PEAK OUTFLOW IS 308. AT TIME 15.75 HOURS

PEAK OUTFLOW IS 435. AT TIME 15.75 HOURS

PEAK OUTFLOW IS 589. AT TIME 15.75 HOURS

TOFFL CUDL FAPD DAMWID

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0

5810 0.0 0.0 0.0



PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLANNATIO ECONOMIC COMPUTATIONS

FLOW IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)

AREA IN SQUARE MILES IS QUARTER A MILLION PER

[illegible]



# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 ..... INITIAL VALUE SPILLWAY CREST TOP OF DAM  
 ELEVATION 577.00 581.90  
 STORAGE 577.00 581.90  
 OUTFLOW 0.00 0.00

RATIO OF PPE	MAXIMUM RESERVOIR DEPTH OVER DAM ACFT	MAXIMUM STORAGE ACFT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
0.60	0.00	0.00	0.00	0.00	15.75	0.00
0.70	0.11	0.11	0.11	0.11	15.75	0.00
0.75	0.24	0.24	0.24	0.24	15.75	0.00



**DATE**  
**FILME**